

BUILDING DEMOLITIONS, SPRINGHILL NS

**T-MCC-2003
Addendum No. 2**

Page 1
February 14, 2020

To All Bidders of Tender T-MCC-2003:

The following addendum applies to this tender and shall be taken into account when preparing a submission.

This Addendum must be acknowledged in the Tender Form.

The following changes or modifications shall be made to the Tender Documents:

TO THE SPECIFICATION:

1. In 2. SCOPE OF WORK, Item 1. Mine Manager's Building item a. add the following after the first sentence.

‘Basement is approximately 1.95 m (6.5’) high.’

2. In 2. SCOPE OF WORK, Item 4. Lamp Cabin Building item a delete

‘Building was single storey brick block construction with wood roof and 1.8 m (6’) concrete foundation. Approx. plan dimensions were 10.5 m x 41 m (34’ x 134).’

And replace with the following

‘The Lamp Cabin Building was two separate buildings which were joined to form one building by a later addition. The entire building was single storey brick block construction with wood roof. The original building at the northeast end was an electrical building with an approx. 1.8 m (6’) basement and a 1.8 m (6’) rock foundation, wood floor on the ground level and a two or more 1.8 m x 1.8 m concrete pedestals for transformers or similar heavy equipment. The original building at the southwest end and the later addition were concrete slab on grade construction. Approx. plan dimensions were 10.5 m x 41 m (34’ x 134).’